

LOUVER CONSTRUCTION

MODEL: SLS-07-3Q0T-F

FRAME: .081" THK. EXTRUDED ALUM. 6063-T5

BLADES: .070" THK. EXTRUDED ALUM. 6063-T5

FASTENERS: #10-16 X 1" PLATED STEEL TEK SCREW

SCREEN: 1/2" MESH X .063 ALUM. WIRE SCREEN IN FRAME

FINISH: KYNAR 500, 2-STEP COLOR AS SELECTED

NOTES:

- I. ALL LOUVERS TO BE FABRICATED 1/4" UNDER LISTED OPENING SIZES UNLESS OTHERWISE SPECIFIED "ACTUAL".
- 2. ALL OPENINGS SIZES TO BE FIELD VERIFIED AND GUARANTEED BY OTHERS PRIOR TO FABRICATION.
- 3. OTHER SURROUNDING FINISHES ARE FOR REFERNCES ONLY AND TO BE SUPPLIED BY OTHES.

Products Group

1855 SOUTH 54TH AVENUE, CICERO, IL. 60650

ARCH/ENGR:

DEPENDABLE PRODUCTS
SINCE 1955

ARCH/ENGR:

DEPENDABLE PRODUCTS
SINCE 1955

CUSTOMER:

REV.	DESCRIPTION	DATE	BY	PROJECT:		TITLE:
						SLS-07/SERIES
				DATE:	DRAWN:	DRWG #:
				SCALE: 1:1	CHKD:	